BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Project Division

SCHEDULE-B

NAME OF THE WORK: Construction Of OutDoor Stadium (phase-1) Survery No.33 in Ward No.13

SI No	Description Of Work	Unit	Qty	Sanctioned Rate ~~Rate To Be Quoted~~	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Sqm	7495.80	6.48	Rupees Six and Forty Eight Paise Only
2	Excavation in Soil with Dozer KSRRB M300-11. Excavation for road way in all types of soil by mechanical cum means including cutting and pushing the earth to site of embankment including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	1124.37	73.44	Rupees Seventy Three and Forty four Paise Only
3	KSRB 2-1.1 : Earthwork in surface excavation in Soft soil for leveling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavatedsurface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. specification. Asper the Directon Of Enggineer -in-charge of the work	Cum	11618.49	269.5	Rupees Two Hundred Sixty Nine and Five Paise Only
4	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Sqm	7495.80	5.40	Rupees Five and Forty paise only
5	KSRRB M300-55. Construction of sub-grade and earthen shoulders with approved material Gravel/Murrum with ail lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications, including cost of earth, watering charges & compaction by vibratory roller to 97% of proctors density) Asper the Directon Of Enggineer -in-charge of the work	Cum	7270.93	357.48	Rupees Three hundred and Fifty seven and Forty Eight Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BMP DIVISION
BENGALURU-560 010

Signature Of The Contractor

Executive Engineer
Dasarahalli Project Division

Scanned by CamScanner

6	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	522.41	188.56	Rupees One hundred Eighty eight and Fifty six Paise Only
7	KSRB-3.2: Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier underand around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration, including cost of chemical, diluting in water to one percent concentration, labour, HOM of equipments, complete as per specifications. (Plinth area of the building at ground floor only shall be measured) Specification Asper the Directon Of Enggineer -in-charge of the work	Sqm	659.89	111.24	Rupees One hundred and Eleven and Twenty Fore Paise Only
8	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892Cum and fine aggregates @ 0.465Cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification Asper the Directon Of Enggineer -in-charge of the work	Cum	86.81	5449.68	Rupees Five thousand foure hundred and Forty nine and Sixty eight Paise Only
9	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification Asper the Directon Of Enggineer -in-charge of the work	Sqm	275.52	316.44	Rupees Three hundred and Sixteen and Forty four Paise Only
10	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge.	Tn	6.66	65455.56	Rupees Sixty Five thousand foure hundred and Fifty five and Fifty Six Paise Only
11	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mix concrete(RMC) for RCC works laid in 15 cms thick layers and well conpacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exlusive of cost of steel and fabrication charges) Ready mix concrete M-20 for raft foundation, coulmn and footing, main ans secondary beams Asper the Directon Of Enggineer -in-charge of the work	Cum	110.92	6349.32	Rupees Six thousand three hundred fourty nine and Thirty two Paise Only
12	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge. {Data Rate sheet enclosed} Asper the Directon Of Enggineer -in-charge of the work	Sqm	59.40	1905.00	Rupees One thousand Nine hundred and Five rupees Only

EXECUTIVE ENGINEER-4
BANGALORE PROJECT DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Project Division

Scanned by CamScanner

	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge	Sqm	23.70	4743.00	Rupees Foure thousand seven hundred and Fourty three rupees Only
14	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	727.38	4521.96	Rupees Foure thousand five hundred and twenty one and Ninty six paise only
15	KSRB 4-1.6 ; Providing and laying in position plain cement concreteof mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, nciuding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification Asper the Directon Of Enggineer -in-charge of the work	Cum	54.60	5876.28	Rupees Five thousand Eight hundred seventy sixe and Twenty eight Paise Only
16	KSRB 2.3: Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification. Asper the Directon Of Enggineer -in-charge of the work	Cum	81.61	137.16	Rupees One hundred thirty seven and Sixteen Paise Only
17	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm. Asper the Directon Of Enggineer -in-charge of the work	Sqm	842.99	2040.12	Rupees Two Thousand fourty and Twelve Paise Only
18	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, Asper the Directon Of Enggineer -in-charge of the work	Mtr	640.20	170.64	Rupees One hundred seventy and Sixty foure paise Only

Executive Engineer
Dasarahalli Project Division

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL DIVISION
BENGALURU-560 010

Scanned by CamScanner